

# MBI Lapendary® Panel Guide Specification Series 4000PS-2012-W, Model #110

## Part I: General

## 1.1 Work Included:

The work consists of furnishing all labor, materials, accessories and equipment necessary to cover all areas shown on the drawings and specified herein with MBI Panels.

# 1.2 Delivery and Storage:

Store this product in unopened cartons in a clean, cool, dry interior space. Cartons and product must be protected against marring, water, dirt or damage during delivery and storage.

## Part II: Product

## 2.1 Product and Manufacturer:

MBI Lapendary® Acoustical Panels exclusively manufactured by: MBI Products Company, Inc. 801 Bond Street

Elyria, Ohio 44035-3318 Phone: 440.322.6500 Fax: 440.322.1900

Website: <a href="www.mbiproducts.com">www.mbiproducts.com</a> Email: <a href="mailto:sales@mbiproducts.com">sales@mbiproducts.com</a>

**2.1.1 Geometric Shape:** Rectangular

2.1.2 Size & Thickness: 2" Thick

(4' x Custom Length)

**2.1.3 Core**: 1.2# Fiberglass

# 2.1.4 Surface Finish:

PVC, Solid Both Sides for High Humidity Environments

**2.1.5 Color:** 10 Available: See Color Card

2.1.6 Edge Shape: Natural

**2.1.7 Edge Construction:** Heat Sealed

## 2.1.8 Acoustical Performance:

RAL A	RAL A10-014 E-400 Mtg.				NRC 0.95	
Hz	125	250	500	1000	2000	4000
APU	0.85	1.04	1.03	1.06	0.69	0.42

# 2.1.9 Incombustability:

Class A per ASTM E84 25/0/50

# 2.1.10 Suspension Provision:

3" Diameter Washer Plates, Painted to Match

## Part III: Execution

# 3.1 Installation

**3.1.1** MBI acoustical panels shall be located and spaced as detailed on reflected ceiling plans and/or detailed on the interior elevation drawings and as indicated on room finish schedule.

## 3.1.2 Suspend Panels From:

(existing construction) (cable) (fasteners [type])

## 3.1.3 Attachment Method:

(heavy duty plastic tie) (coated wire tie) (beam clamps) (washer plates) (cable)

# 3.1.4 Workmanship

The acoustical system shall be installed only by an approved contractor.

All work shall be completed in a workman like manner. All panels shall be properly installed and left in a clean, sanitary condition. Contractor shall remove and dispose of shipping containers and debris.