

# MBI SPECTRUM® PVC Panel Guide Specification Series 2900PS-2065-W

Part I: General

#### 1.1 Work Included:

The work consists of furnishing all labor, materials, accessories and equipment necessary to cover all areas shown on the drawings and specified herein with MBI Panels.

# 1.2 Delivery and Storage:

Store this product in unopened cartons in a clean, cool, dry interior space. Cartons and product must be protected against marring, water, dirt or damage during delivery and storage.

## Part II: Product

### 2.1 Product and Manufacturer:

MBI SPECTRUM® Acoustical Panels exclusively manufactured by: MBI Products Company, Inc. 801 Bond Street Elyria, Ohio 44035-3318

Phone: 440.322.6500 Fax: 440.322.1900

Website: www.mbiproducts.com Email: sales@mbiproducts.com

2.1.1 Geometric Shape: Rectangular

**2.1.2 Size & Thickness:** <u>2" Thick</u> (Maximum size up to 4' x 10')

**2.1.3 Core:** <u>1.65# Fiberglass</u>

**2.1.4 Surface Finish:** 2.5 mil PVC, Solid Both Sides

**2.1.5 Color:** <u>10 Available: See Color Card</u>

**2.1.6 Edge Shape:** Natural/Square

**2.1.7 Edge Construction:** Heat Sealed

## 2.1.8 Acoustical Performance:

RAL A95-134 Type "A" Mtg.					NRC 0.90	
Hz	125	250	500	1000	2000	4000
APU	0.35	0.80	1.19	1.02	0.63	0.32

## 2.1.9 Incombustibility:

Class A per ASTM E84 25/0/50

# 2.1.10 Suspension Provision:

<u>3" Diameter Washer Plates, Painted to Match</u> Fender Washers by Others

## Part III: Execution

#### 3.1 Installation

**3.1.1** MBI acoustical panels shall be located and spaced as detailed on reflected ceiling plans and/or detailed on the interior elevation drawings and as indicated on room finish schedule.

# 3.1.2 Suspend Panels From:

(horizontal stretched wire or cable)
(fasteners [eye screws] [L-Hook])
(existing construction)
(see MBI drawings for more information)

#### 3.1.3 Attachment Method:

(coated wire tie) (stainless steel tie)
(see MBI drawings for more information)

## 3.1.4 Workmanship

The acoustical system shall be installed only by an approved contractor.

All work shall be completed in a workman like manner. All panels shall be properly installed and left in a clean, sanitary condition. Contractor shall remove and dispose of shipping containers and debris.